

تأهيل البرج الحميدي ومحتوياته - السراي الكبير
جدول الاسعار

Item	Description	Unit	QTY	Unit Price L.L	Total Price L.L
	CHAPTER 1 - Electrical Works				
1.1.1	Supply and install Deye Inverter 6KW	No.	1		
1.1.2	Supply and install Deye Batteries 5kw	No.	2		
1.1.3	Supply and install Electrical Panel Board for inverter with all related accessories and protection	No.	1		
1.1.4	Install new led light 15W E27 and connect it to existing panel	No.	6		
1.1.5	Install new led light 15W E27 and connect it to clock power outlet	No.	4		
	CHAPTER 2 - WINDOWS				
2.1.1	Replace Window single tempered glass.	m2	17.00		
2.1.2	Window single Glass - Maintenance	m2	14.00		
2.1.3	Wooden Frame - New Ornament frame similar to existing	m2	9.00		
2.1.4	Wooden Frame - Rehabilitation of Ornament frame similar to existing	m2	22.00		
2.1.5	Install New Perforated Steel Window Panels for Opening of Speaker Room with Paint	No.	4.00		
	CHAPTER 3 - WOODEN DOORS				
3.1.1	Rehabilitation of Ornamental Wooden Door OWD - 60 with Paint	No.	4.00		
3.1.2	Rehabilitation of Wooden Door WD - 17 with Paint	m2	2.40		

Item	Description	Unit	QTY	Unit Price L.L	Total Price L.L
	CHAPTER 4 - FINISHING WORKS				
4.1.1	Wall Paint Works Wall paint include prepare the surfaces and treat these surfaces so the surfaces be able to receive the paints, The paint should be from the best quality (Tinol) The surfaces should be smooth before layers The final layer and the permit from the Engineer should be secured before starting the final layer All works and items should be as per the Engineer instructions	m2	270.00		
4.1.2	Paint existing stair + balustrades (Tinol)	No.	1.00		
4.1.3	Install New Cat Ladder for Clock Maintenance	No.	1.00		
4.1.4	Paint existing steel Fences (Tinol)	No.	1.00		
4.2.1	Rehabilitate Natural Stone Facades: Rehabilitate works on natural stone facades Work to include: - Determine the location of the damaged stone walls and location of dampness - Treat the dampness and the causes - Repair the stone by renewing the damaged and replace it with new ones with same stone - Clear the place and infill in between the coarse (Lining) - All works as instructed by the Engineer	m2	368.00		
4.2.2	Repair internal plaster	m2	50.00		
4.2.3	Polishing for existing floor tiles	m2	50.00		
4.2.4	Polishing for existing floor tiles next to Fountain	m2	350.00		
4.2.5	Polishing for existing Fountain	No.	1.00		
4.2.6	Water Repellent for Facades	m2	368.00		
4.2.7	Maintain roof water proofing with all related works	No.	1.00		
4.2.8	Rehabilitation of fountain system including replacement of pump with related electrical work and piping system	LSM	1.00		
	CHAPTER 5 - CLOCK MECHANISM				
5.1.1	Supply and install Swiss Made Clock, Fully assembled in Switzerland as per technical specification file.	No.	4		
TOTAL CARRIED TO PRICE SUMMARY					
VAT					
Grand Total Price Summary					
Grand Total Price Summary in Letters					